

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-039-20460-0000 (of this well)
Lease Owner D/FW Oil & Gas, Inc.
Address Suite 603 University Tower, 6440 No. Central Expressway, Dallas Texas
75206
Lease (Farm Name) ROBERTSON "B" Well No. 1
Well Location SW SW Sec. 23 Twp. 3S Rge. 27W (E) (WX)
County Decatur Total Depth 3800' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 4:00 a.m., 10-18-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Gerrell Veatch Address 1207 Court Place, Colby, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name D/FW Oil & Gas, Inc.

Address Suite 603 University Tower, 6440 No. Central Expressway, Dallas Texas
75206

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: October 23, 1979

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1979 10-25-79
CONSERVATION DIVISION
WICHITA, KANSAS

15-039-20460-0000

CONTRACTOR'S WELL LOG

OPERATOR:	D/FW Oil & Gas, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Robertson "B" #1
LOCATION:	SW SW, Section 23-3S-27W Decatur County, Kansas
SPUD DATE:	October 12, 1979
COMPLETION DATE:	October 18, 1979

0	250	Clay, sand and shale
250	2004	Shale and sand
2004	2187	Sand and shale
2187	2218	Anhydrite
2218	2980	Shale
2980	3680	Lime and shale
3680	3800	Lime
	3800	Rotary Total Depth

Spud hole at 7:30 p.m., October 12, 1979. Drilled 250' of 12 1/4" hole. Ran 6 joints of 8-5/8" - 20# casing. (Talley 242') Set at 249' R.B. with 180 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 1:15 a.m., October 13, 1979.

T.D. 3800'. Set 1st plug at 1300' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 4:00 a.m. October 18, 1979.

SAMPLE TOPS:

Anhydrite 2187'
B/Anhydrite 2218'

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1979

CONSERVATION DIVISION
Wichita, Kansas

10-25-79


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Robertson "B" #1, SW SW, Section 23-3S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 23rd day of October, 1979.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-039-20460-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
JAMES B. DOUGLAS

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

October 23, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Robertson
Description	SW SW
Section	23-3S-27W
County	Decatur
Total Depth	3800'
Plugging Contractor	Abercrombie Drlg.

D/FW Oil & Gas, Inc.
6440 North Central Expressway, 603 University Tower
Dallas, Texas 75206

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,

J. LEWIS BROCK, Administrator

Gilbert Balthazor, P.O. Box 9, Palco, KS 67657 is hereby assigned to supervise the plugging of the above named well.