

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 039 - 20457-00-00 (of this well)
Lease Owner Zenith Drilling Corporation
Address 200 W. Douglas, Suite 600, Wichita, Kansas 67202
Lease (Farm Name) KRISEK Well No. 1
Well Location SE SE NW Sec. 22 Twp. 3 Rge. 27 (E) (W) X
County Decatur Total Depth 3815' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 9:15 p.m., 6-11-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address Friendly Acres, #74, Colby, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Zenith Drilling Corporation

Address 200 W. Douglas, Suite 600, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent 6-22-79

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: June 21, 1979

STATE RECEIVED
CORPORATION COMMISSION
JUN 22 1979

CONSERVATION DIVISION
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

OPERATOR: Zenith Drilling Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Krisek #1
 LOCATION: SE SE NW, Section 22-3-27,
 Decatur County, Kansas
 SPUD DATE: June 04, 1979
 COMPLETION DATE: June 11, 1979

0	150	Clay and sand
150	287	Shale
287	2197	Shale and sand
2197	2228	Anhydrite
2228	2504	Shale and sand
2504	2662	Shale
2662	2942	Shale and lime
2942	3105	Shale
3105	3295	Shale and lime
3295	3572	Lime and shale
3572	3610	Lime
3610	3628	Shale and lime
3628	3740	Lime and shale
3740	3815	Lime
	3815	Rotary Total Depth

Spud hole at 9:15 p.m., June 04, 1979. Drilled 287' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 20# new casing. Set at 286' R.B. with 210 sacks of Class A cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 3:30 a.m., June 05, 1979.

T.D. 3815'. Set 1st plug at 1350' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:15 p.m., June 11, 1979.

SAMPLE TOPS:

Anhydrite 2197'
 B/Anhydrite 2228'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

STATE RECEIVED
 JUN 22 1979
 CONSERVATION COMMISSION
 6-22-79

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Krisek #1, SE SE NW, Section 22-3-27, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 21st day of June, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

State of Kansas



15-039-20457-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
Telephone (316) 263-3238

June 14, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Krizek
Description	SE SE NW Sec. 22-3S-27W
County	Decatur
Total Depth	3815'
Plugging Contractor	Abercrombie Drilling, Inc.


Zenith Drilling Corporation, Inc.
200 W. Douglas, Suite 600
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.