

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Herman L. Loeb

Address: PO Box 524 Lawrenceville IL 62439

Phone: (812) 853-3813 Operator License #: 3273

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/16/04 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet) Simpson Depth to Top: 4459' Bottom: 4470' T.D. 4470'

API Number: 15-NA007-20197-00-00

Lease Name: Skinner

Well Number: #1

Spot Location (QQQQ): - NE - SW - NE

1650' Feet from North / South Section Line

1650' Feet from East / West Section Line

Sec. 8 Twp. 31S S. R. 14 East West

County: Barber

Date Well Completed: NA 2-7-92

Plugging Commenced: 8/16/04

Plugging Completed: 8/20/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes of 13", 8 5/8", and 5 1/2" with corresponding depths.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

MIRU Clarke Corp. Set CIBP @ 4400', dump 2 sxs of Portland Cement w/ dump bailer. Isolate csg. leak @ 3570' and squeeze w/ 100 sxs class A cement. Isolate csg. leak @ 2040' and squeeze w/ 100 sxs class A. Perforate 789' to 790'. Pump 225 sxs 60/40 6% gel, circulate cement to surface.

RECEIVED

Name of Plugging Contractor: Clarke Corp. License #: 5105


Address: 107 W. Fowler, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Herman L. Loeb

State of Kansas County, Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Alan Vratil

(Address) 509 N. Cedar, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 23 day of Aug, 2004

Glenda Morrison Notary Public My Commission Expires: 11/30/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202