

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Resource Operations, Inc. Address: P.O. Box 466 Chase, Kansas 67524 Phone: (620) 938 2982 Operator License #: 30364 Type of Well: Oil Docket #: The plugging proposal was approved on: Virgil Clothier (KCC District Agent's Name) Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. 3269'

API Number: 15-053-00740-00-00 Lease Name: Schroeder C Well Number: 3 Spot Location (QQQQ): C - SW - NW 1980 Feet from North / South Section Line 660 Feet from East / West Section Line Sec. 34 Twp. 16 S. R. 10 East West County: Ellsworth Date Well Completed: 7-20-43 Plugging Commenced: 8-16-04 Plugging Completed: 8-18-04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes 8-5/8" and 5-1/2" with depths 333' and 3251' respectively.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Plugged off bottom with sand to 2930' and 5 sacks cement. Perforated 5-1/2" casing at 1300', 1000' and 380'. Ran 2" tubing to 1300', pumped 35 sacks cement, pulled up to 1000', pumped 35 sacks cement, pulled up to 380' and circulated 75 sacks cement. Topped off with 10 sacks cement. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Resource Operations, Inc.

State of Kansas County, Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 25th day of August 2004

[Handwritten Signature] Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 26 2004

KCC WICHITA

[Handwritten Initials]