

15-039-20709-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 10 TWP. 3 S RGE 29W ~~E/W~~
 Location as in quarters or footage from lines:
3190' FSL & 660' FEL of section

			X

Lease Owner S & W Drilling Co., Inc.
 Lease Name 10-G G. Smith Well No. 10-8
 Office Address P O Box 132 Oberlin, Ks. 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 4-17-84
 Application for plugging filed 4-11-85
 Plugging commenced 9:30 AM 4-10-85
 Plugging completed 11:28 AM 4-10-85
 Reason for abandonment of well or producing formation non-commercial

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing Depth to top 3635 bottom 3638 T.D. 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Ogallala	water	0	200	8 5/8	247	0
Dakota	water	1250	1600	4 1/2	3807	0
Lansing	oil	3613	3812	4 1/2	3807	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeeze down 4 1/2" casing with 4 sx hulls in 12 bbl water, 60 sx 50/50 pozmix 6% gel & 3% CC in 16.3 bbl slurry, 27 bbl gel, mixed 1 sack in 3 bbl water, perfs squeezed off at this point, state plugger had us drop 4 1/2" plug and squeeze it down with another 1 1/2 bbl of 50/50 pozmix 6% gel & 3% CC. Pressure holding steady at 2000#, released pressure with no flow back.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Decatur, ss.

James L Reeves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L Reeves
P O Box 16 Oberlin, Ks 67749
 (Address)

SUBSCRIBED AND SWORN TO before me this 11 day of April, 19 85

Thomas D. Deane
 Notary Public.

My Commission expires: 12-22-86

RECEIVED
 STATE CORPORATION COMMISSION

APR 12 1985
4-12-85
 CONSERVATION DIVISION
 Wichita, Kansas