


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County. Sec. 9 Twp. 3S Rge. 29 (W)
Location as "NE/CNW/SW" or footage from lines. C NE NE
Lease Owner Anderson-Prichard Oil Corp.
Lease Name August Zander Well No. 1
Office Address Box 142, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Feb. 28, 19 59
Application for plugging filed Sept. 11, 19 59
Application for plugging approved Sept. 14, 19 59
Plugging commenced Sept. 15, 19 59
Plugging completed Sept. 19, 19 59
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well ^{PB} 3650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	224'	None
				4 1/2" OD	3775'	3115'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T. D. 3650'.
Plugging started 9-15-59. Finished 9-19-59.
Plugged off bottom and sanded back to 3635'. Dumped 3 sacks of cement. Worked and shot pipe. Shot 4 1/2" casing at 3,115'. Laid down pipe and plugged well as follows: Mudded to 220'. Set rock bridge and dumped 25 sacks of cement. Filled hole with mud to 35'. Set rock bridge and mixed 10 sacks of cement for cap on well.
Well completed.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1959

CONSERVATION DIVISION
Wichita, Kansas

9-23-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Gerald M. Dougherty (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. ANDERSON-PRICHARD OIL CORPORATION

(Signature) By: Gerald M. Dougherty
Box 142, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 59

My commission expires December 4, 1962

Verdella M. Hankins
Notary Public.



PLUGGING

File Sec. 9 T 3 R 29W

Book Page 3 Line 7