

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-039-00552-00-00

API NUMBER NA

LEASE NAME Pollnow Unit

WELL NUMBER 11

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 08 TWP. 03 RGE. 29 ~~XX~~ or (W)

COUNTY Decatur

Date Well Completed 10/30/55

Plugging Commenced 11/27/91

Plugging Completed 11/27/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Te-Pe Oil & Gas Company

ADDRESS P.O. Box 522, Canton, Kansas 67428

PHONE# (316) 628-4428 OPERATORS LICENSE NO. 5920

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 27, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing-KC Depth to Top 3711 Bottom 3940 T.D. 3940

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Oil & Water	221	GL	8-5/8	221	0
		3938	GL	5-1/2	3938	0

12-05-91
DEC 05 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Run tubing to 2450'. Pump in 100 sacks 65/35 Pozmix 10% Gel with 300# hulls. Pull to 810'. Squeeze bottom with 100 sacks. Circulate 5-1/2 casing full of cement. Pull tubing. Squeeze 130 sackd 65/35 Pozmix 10% Gel down 5-1/2 casing. Squeeze 70 sacks 65/35 Pozmix 10% Gel and 100# hulls down 5-1/2 X 8-5/8 annulus. Holes in 5-1/2 casing at 1250' and 2167' to 2423'.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Servicing, Inc. License No. 3152

Address P.O. Box 115, Oberlin, Kansas 67749-0115

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Pe Oil & Gas Company


STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 522, Canton, Ks. 67428

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 19 91



Cynthia G. Reimer
Notary Public

My Commission Expires: May 15, 1994