

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-039-00548-00-00

API NUMBER 7/11/58

LEASE NAME Pollnow Unit

WELL NUMBER 6

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 4 TWP. 03 RGE. 29 ~~XXX~~ (W)

COUNTY Decatur

Date Well Completed 7/11/58

Plugging Commenced 4/15/92

Plugging Completed 4/15/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Te-Pe Oil & Gas Company

ADDRESS P.O. Box 522, Canton, Kansas 67428

PHONE# (316) 628-4428 OPERATORS LICENSE NO. 5920

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/8/92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing Depth to Top 3707 Bottom 3915 T.D. 3926

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil & Water	229.31	0	8-5/8	229.31	0
		3915	0	4-1/2	3915	0
4 1/2" casing	squeezed with 550 sacks				2163 stage collar in 4 1/2" casing.	
at 2657'					Black Magic circulated to surface.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Rig up Halliburton. Pump 250 sacks 65/35 Pozmix 10% gel mixed with 500# hulls down 4 1/2" casing. Shut in with 500# pressure on casing. Pump 5 sacks 65/35 Pozmix 10% gel down 8-5/8"-4 1/2" annulus. Shut in with 300# pressure. Pump 45 sacks more 65/35 Pozmix 10% gel down 4 1/2" casing Shut in pressure 700#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Te-Pe Oil & Gas Company License No. 5920

Address P.O. Box 522, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Pe Oil & Gas Company

STATE OF Kansas COUNTY OF McPherson, ss.


Terry P. Bandy

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 522, Canton, Kansas 67428



SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 92

Cynthia G. Reimer
Notary Public

My Commission Expires: May 15, 1994

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1992
CONSERVATION DIVISION
Wichita, Kansas

4-27-92

Form CP-4
Revised 05-88

DRILLERS' LOG

Well Owner: Anderson-Prichard Oil Corporation
 Farm Name: Lotker Well No. 1
 Commenced: 5/29/58
 Completed: 6/6/58
 Total Depth: 3925'
 Casing: 8 5/8" @ 225' cemented
 4 1/2" @ 3898' cemented

C NW SE
 Sec. 4-35-29W
 Decatur County, Kansas

Elevation:
 Production:

Contractor: Glenn W. Peel

Conservation Division
 500 Broadway Building
 1014 K
 Wichita, Kansas

Figures below indicate bottoms of formations:

	0	225
Clay and shale		172#
Shale and shells		2160
Shale		2175
Lime		2425
Shale		2460
Anhydrite		2550
Shale		3140
Shale and lime		3255
Lime		3705
Shale and lime		3742
Lime		3925
Lime and shale		3925
Total Depth		

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY Jack Mattar

SUBSCRIBED AND SWORN to before me this 9th day of June, 1958

My commission expires: April 27, 1960

Ruth Brunk
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

APR 27 1992
 4-27-92
 CONSERVATION DIVISION
 Wichita, Kansas