

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02755-00-00
Spot: S2SESE Sec/Twnshp/Rge: 32-8S-24W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: HOLLEY UNIT Well #: 11-2
County: GRAHAM Total Vertical Depth: 3962 feet

Operator License No.: 30420
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR
Address: 30-38 48TH STREET
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3962 100 SX CMT
SURF Size: 8.625 feet: 213 175 SX CMT

#128⁷⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES Phone: (718) 274-3134

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool at 1930' w/200 sxs.
CIBP set at 3650'. Haliburton squeezed. Dakota leaks 1730' and did not drill out.
08-16-2004 - Ran in with notch collar - tagged cement at 1590' - drilled sample cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2004 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1590'.
Allied pumped 120 sxs 60/40 pozmix - 10% gel with 300# hulls - cement circulated.
PTOH. Allied squeezed with 80 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside. Allied pumped 50 sxs cement with 200# hulls.
Max. P.S.I. 100#. S.I.P. 503.
Note: Dakota squeeze job not drilled out - TOC 1590'.

Perfs:

Top	Bot	Thru	Comments
3850	3949		

RECEIVED
AUG 23 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS KEITH #A-2. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 8-24-04

INV. NO. 2005060394

AUG 18 2004

IMPERIAL OIL

#2 KEITH 'A'

32-8-24W
C S2 SE SE

Contr.

IMPERIAL OIL

GRAHAM

County

E 2443RB

Comm.

Comp.

3-2-56

IP

414 BOPD/LANS

Tops	Depth	Datum
LANS	3775	-1332
TD	3962	-1519

Casing

5" 3962

DST 3914-37/2 HR, 420' GAS,

105' OCM, BHP 540#

DST 3940-62/2 HR, 300' GAS,

50' H OCM, 60' OIL, BHP 1265#

PERF 24/3945-49: SWB 1 BOPH/

2 HR: 30/3926-31: SWB 2 BOPH

/7 HR: ACID 3000: SWB 34

BOPH/16 HR:

HOLLY NW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MAOICED