

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24706-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 30-13S-16W
4840 feet from S Section Line, 440 feet from E Section Line
Lease Name: GORE T Well #: 4
County: ELLIS Total Vertical Depth: 3560 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: PO BOX 70 234 W. 11TH, STE A
HAYS, KS 67601

PROD Size: 5.5 feet: 3559 125 SXS CMT
SURF Size: 8.625 feet: 1110 400 SXS CMT

\$115.⁷⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2004 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2004 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Shot 5 1/2" casing off at 1900' - pulled 3 joints.
Spotted first plug at 1800' w/130 sxs cement with 300# hulls.
Pulled casing to 1200' - spotted 45 sxs cement with 100# hulls.
Pulled casing to 588' - spotted 40 sxs cement.
Pulled casing to 188' - spotted 30 sxs cement.
Pulled all casing and topped surface pipe with 20 sxs cement.
Total of 265 sxs 60/40 pozmix - 10% gel and 400# hulls.

Perfs:

Top	Bot	Thru	Comments
3510	3512		
3411	3417		

RECEIVED
AUG 25 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Roger L Moses
(TECHNICIAN)

INVOICED

DATE

8-26-04

INV. NO.

2005060404

Form CP-2/3

AUG 23 2004

STATE KANS COUNTY ELLIS
 FIELD HERZOG (LANSING/ARBUCKLE)
 OPER DAMAR RESOURCES
 WELL 4 GORE T
 API 15-051-24706-0000
 SPUD 11/30/1990
 DTD 3560 LTD 3560 FTD ARBUCKLE

30-13S-16W
 NE NE NE

WELL CLASS 4840FSL 440FEL SEC
 STATUS DO
 COMP OIL 01/11/1991
 PSTD 3506



LOC 2 1/2 MI NE VICTORIA, KS

Petroleum Information Corporation

* IPP 10 BOPD 273 BW GTY 35
 PROD ZONE: ARBUCKLE 3485-3490

EL: 1976 KB 1975 DF 1971 GR

CSGS: 8 5/8 @ 1110 W/ 400 SACKS
 5 1/2 @ 3559 W/ 125 SACKS
 DRLG COMP 12/7/90 RIG REL 12/8/90
 DSTS: DST 1 3458-3491 ARBUCKLE
 REC 150 FT OGCM 120 FT SOWCM
 INIT OP 15M IFP 44 FFP 44
 FINAL OP 45M IFP 77 FFP 133
 ISIP 962 45M FSIP 940 1H
 PERFS: ARBUCKLE PERF W/ 4/FT 3510-3512
 TREATMENT & TSTG RESULTS NOT RPTD
 BRPG @ 3506
 ARBUCKLE PERF 3485-3490
 ACID 250 GALS 15%
 NO CORES
 OPER ADDRESS: BOX 70, HAYS, KS 67601
 CONTR: WESTERN KANSAS DRLG

LOG TOPS:
 STONE CORRAL 1110 +866
 TOPEKA 2980 -1004
 HEEBNER 3195 -1219
 TORONTO 3214 -1238
 LANSING 3244 -1268
 BSE KANSAS CITY 3462 -1486
 ARBUCKLE 3484 -1508
 TD 3560 -1584

KS 5-021901