

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21221-00-00
Spot: NESWNW Sec/Twnshp/Rge: 26-17S-14W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: LOGAN Well #: 1
County: BARTON Total Vertical Depth: 3347 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3338 w/75 sxs cmt
SURF Size: 8.625 feet: 828 w/200 sxs cmt

#108⁷⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/03/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2004 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 1500'.
Circulated with 215 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
POOH. Tied onto casing and pumped 100 sxs cement with 300# hulls.
Cement circulated up backside - shut in.
Pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
AUG 25 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris

(TECHNICIAN)

INVOICED

DATE 8-26-04

INV. NO. 2005060403

Form CP-2/3

AUG 23 2004

HUMMON OIL CO. & LEONARD ROPFOGEL #1 LOGAN 26-17-14W NE SW 1/4
 1725 VICKERS-KSB&T BLDG., WICHITA, KS.
 CONTR DUKE DRLG. CO. CTY BARTON
 GEOL BOB JINKINS FIELD CARROLL SE EXT (1/2 N)
 E 1859 KB CM 8/23/77 CARD ISSUED 11/3/77 IP P 35 BOPD + 84 SWPD
 ARB 3338-57

API 15-009-21,221

LOG	TOPS	DEPTH	DATUM
*ANH		818	+1041
*B ANH		840	+1019
HOW		2713	- 854
TOP		2787	- 928
QH		2939	-1080
TOR		3059	-1180
DOUG		3050	-1191
LANS		3099	-1240
BKC		3305	-1446
ARB		3340	-1481
RTD		3346	-1487
LTD		3347	-1488
DDTR		3357	-1498
*DRILLERS TOPS			

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

8-5/8" 828/200sx, 5 1/2" 3338/75
 DST (1) 3098-3118/30-30-30-30,
 SIP 51-44#, FP 36-36#, BHT
 DST (2) 3144-77/30-30-30-30, 15'
 OIL SPTS, FSIP 59#, FP 24-44
 BHT 108°
 DST (3) 3223-3270/30-30-30-30,
 SP M (GSO) SIP 66-59#, FP
 BHT 101°
 DST (4) 3298-3342/30-30-30-30,
 SIP 1027-991#, FP 51-31
 DST (5) 3297-3346/30-30-30-30,
 VHOOM, 60' HOOM, 60'
 66-110#
 MICT - CO, AC 50, SDC, 4
 20 GO, DD 3354, AC 280, 20/10
 (OVER)

FILE
 15010000