

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14540-00-00
Spot: N2SESW Sec/Twnshp/Rge: 14-20S-11W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: LANGFELD Well #: 3
County: BARTON Total Vertical Depth: 3290 feet

Operator License No.: 31647
Op Name: CHURCHHILL, KIM DBA K.C. OPERATI
Address: 534 S E 70 AVE.
ELLINWOOD, KS 67526

CIBP Size: feet: 3240
PROD Size: 5.5 feet: 3280 125 SX CMT
SURF Size: 10.75 feet: 223 200 SX CMT

\$106⁹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 08/12/2004 12:45 PM

Witness Type: COMPLETE (100%)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Cut holes at 1400' - 450'.
Ran tubing to 1500'.
Pumped 200 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Pulled to 750'.
Pumped 80 sxs cement - cement circulated inside and out.
POOH. Tied onto casing and pumped 40 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
AUG 26 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS LANGFELD 1B. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

INVOICED

DATE 8-26-04

INV. NO. 2005060442

AUG 23 2004

D R BUCHANAN ET AL #1B LANGFELD 14-20-11W
 CNL SE SW


Contr. _____ BARTON County

E 1762 Comm. 7-11-40 Comp. 7-23-40 IP 3000 BOPD

Tops	Depth	Datum
ARB	3279	
TD	3290	

Casing
 10" 223

3100' OIH



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

12 10 1940