

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20954-00-00  
Spot: SENESE Sec/Twnshp/Rge: 14-9S-23W  
1650 feet from S Section Line, 350 feet from E Section Line  
Lease Name: BETHEL *KCC  
BEM  
8-24-04* Well #: 1  
County: GRAHAM Total Vertical Depth: 3874 feet

Operator License No.: 30537  
Op Name: VENTURE RESOURCES, INC.  
Address: 2110 S. GILPIN PO BOX 101234  
DENVER, CO 30250

PROD Size: 4.5 feet: 3868 w/175 sxs cmt  
SURF Size: 8.625 feet: 207 w/135 sxs cmt

*\$125<sup>91</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2004 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: RON MACKEY Company: VENTURE RESOURCES, INC. Phone: (785) 623-0328

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls - 11 sxs gel spacer.  
Perforated casing at 1150' - 1975'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/06/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Swaged onto 4 1/2" - mixed and pumped 40 sxs cement with 300# hulls,  
followed with 11 sxs gel spacer.  
Topped with 200 sxs cement with 150# hulls.  
Max. P.S.I. 300#. S.I.P. 150#.  
Hooked onto annulus and pumped 70 sxs cement.  
S.I.P. 50#.

RECEIVED  
JUL 09 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

INVOICED

DATE 8-24-04

INV NO. 2005060397

Form CP-2/3

JUL 07 2004

NO. 47

DATE

MAOICED

ASSOCIATES OIL & GAS, INC. & #1 BETHELL 14-9-23W  
 BILL J. PORTER SUITE 501, 120 SO. MARKET, WICHITA, KS. SE NE SE  
 CONTR DREILING OIL, INC. CITY GRAHAM

GEOL \_\_\_\_\_ FIELD MARSHALL TAW  
 E 2343 KB CM 4/19/78 CARD ISSUED 7/7/78 IP P 99 BOPD + 5% W  
 LANS 3804-07

+	+	+	+
+	+	+	+
+	+	+	+

API 15-065-20,954

LOG	TOPS	DEPTH	DATUM
ANH		1940	+ 403
HEEB		3615	-1272
TOR		3636	-1293
LANS		3648	-1305
BKC		3868	-1325
LTD		3870	-1527
RTD		3874	-1531

8-5/8" 207/135sx, 4 1/2" 3868/175sx  
 DST (1) 3787-3810/30-45-60-45, 450' CGO  
 380' SMGO, SIP 583-563#, FP 66-133#  
 199-265#, BHT 107°  
 DST (2) 3807-3870/30-30-30-30, 30' M +  
 SSO, SIP 118-103#, FP 59-59#, 66-  
 77#, BHT 108°  
 MICT - PF 3804-07. SWB DRY, AC 250, SWB  
 LD, SWB AVG 8.63 BOPH/3 HRS, AC 200,  
 REC LD, SWB AVG 16.50 BOPH/3 HRS, AC  
 500, SWB PT LD, FU 50' OIL, AC 1300,  
 REC LD, SWB 7.59 BO/8 HRS, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS