

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02758-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 32-8S-24W
1650 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HOLLEY UNIT Well #: 9-2
County: GRAHAM Total Vertical Depth: 3974 feet

Operator License No.: 30420
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR
Address: 30-38 48TH STREET
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3974 100 SX CMT
SURF Size: 8.625 feet: 213 175 SX CMT

8129¹⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2004 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES Phone: (785) 625-8360

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 600# hulls.
06-10-1985 - Well had CIBP set at 3650'. Squeezed with 200 sxs.
Did not drill out. Displaced to 2100'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2114'. Tagged cement.
Allied pumped 160 sxs 60/40 pozmix - 10% gel with 500# hulls - cement circulated.
PTOH. Allied squeezed with 15 sxs cement.
Max. P.S.I. 900#. S.I.P. 900#.
Hooked up to backside. Allied pumped 50 sxs cement with 100# hulls.
S.I.P. 0#.

RECEIVED
AUG 23 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3850	3945		

Remarks: LEASE ALSO KNOWN AS KEITH #B-2. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

102

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE

8.24.04

INV. NO.

2005060394

AUG 20 2004

IMPERIAL OIL

#2 KEITH 'B'

32-8-24W
S2 NW SW

Contr. IMPERIAL OIL

GRAHAM County

E 2450RB Comm. 2-24-56 Comp. 3-30-56 IP 331 BOPD

Tops	Depth	Datum
ANH	2140	310
LANS	3784	-1334
TD	3974	-1524

Casing
8" 213
5" 3974

DST 3932-50/1 HR, 2100'
GAS, 100' H OCM, 100' OIL
BHP 740#
PERF 36/3938-14: ACID 4000
SWB 21 BOPH/8 HR
HOLLEY NW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MAOICED