

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-20450-00-00  
Spot: NWNWNWSE Sec/Twnshp/Rge: 33-28S-35W  
2540 feet from S Section Line, 2340 feet from E Section Line  
Lease Name: BAUGHMAN S Well #: 2  
County: GRANT Total Vertical Depth: 3030 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

PROD Size: 4.5 feet: 3029 WITH 225 SX CMT  
SURF Size: 8.625 feet: 768 WITH 400 SX CMT

*\$98.48*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2004 9:45 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS. PLUG AT 1800' WITH 40 SX CMT IF POSSIBLE. PLUG AT 780' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2004 11:45 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 3005'. PUMP 20 SX CMT & 200# HULLS ON BOTTOM. 1ST PLUG PULL CASING TO 790'. LOAD HOLE WITH MUD & SPOT 50 SX CMT. 2ND PLUG PULL TO 300' & SPOT 30 SX CMT. 3RD PLUG PULL TO 30' & SPOT 10 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2933	2945		
2905	2927		
2881	2891		

RECEIVED  
AUG 23 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT. RECOVERED 1243' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
AUG 19 2004  
KCC Dodge City

Signed

*[Signature]*  
(TECHNICIAN)

INVOICED

DATE

8.24.04

INV. NO.

2005060395

*[Signature]*  
Form 100-273