

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00179-00-00
Spot: SESENW Sec/Twnshp/Rge: 13-21S-33W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: WARE Well #: 1-13
County: FINNEY Total Vertical Depth: 2645 feet

Operator License No.: 32356
Op Name: INTERMOUNTAIN REFINING CO, INC
Address: PO BOX 35
FARMINGTON, NM 87499

CIBP Size: feet: 1400 WITH 2 SX CMT
PROD Size: 4.5 feet: 2645 WITH 75 SX CMT
SURF Size: 7 feet: 342 WITH 125 SX CMT

#85⁹⁶

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/17/2004 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: LOCATE HOLES IN 4 1/2". CIBP @ TOP OF FISH & 2 SX CMT OR RUN TUBING TO 2000'. PUMP 100# HULLS & 20 SX CMT. WAIT ON CMT TO TAG. IF NEEDED PERFORATE AT 1200'. CASING VOLUME + 80 SX CMT. IF CIRCULATION IS ESTABLISHED CIRCULATE WELL FROM 1200' TO SURFACE. PUMP 150 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2004 11:45 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 2640'. 1ST PLUG SET CIBP @ 1400' & 2 SX CMT. 2ND PLUG PERFORATE AT 1200'. PUMP 145 SX CMT DOWN 4 1/2" CASING. 80 SX CMT OUT + CASING VOLUME. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 125#. 3RD PLUG PUMP 105 SX CMT DOWN ANNULUS. MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 225#.

Perfs:


Top	Bot	Thru	Comments
2623	2640		
2589	2594		

RECEIVED
AUG 23 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED

DATE 8-24-04
INV. NO. 2005060393