

4-032180

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-11

API Number: 15-039-20,694 -00-00

NE SE /4 SEC. 10 , 03 , 29 W
1980 feet from S section line
660 feet from E section line

Operator license# 6593 Lease: Ufford Bertha Well # 1

Operator: Coastal Oil & Gas County: Decatur

Address: 9 Greenway - #2751 Well total depth 3915 127.23 feet
Houston, Texas 77046 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 289 feet

Aband. oil well , Gas well , Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 11 Month: October Year: 1996

Plugging proposal received from: Jerry Colburn

Company: Coastal Oil & Gas Phone: _____

Were: Order 160 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part [], None []

RECEIVED
OCT 25 2 00 PM '96
10-25-96

Completed: Hour: 10:15 A.M., Day: 11, Month: October, Year: 1996

Actual plugging report: 8 5/8" set at 289 w/225 sxs cwc. 4 1/2" set at 3911' with 150 sxs.
D.V. set at 2399' with 425 sxs cwc. Prod. perfs 3657' - 3661'. PBTD 3868'. Squeezed 4 1/2"
with 50 sxs cement followed with 10 sxs gel followed with 60 sxs cement. Hole locked up at
1200# P.S.I. Held. Tested backside to 300#, cement at surface. Plug complete.

Remarks: Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)
Form CP-2/3

INVOICED
DATE 10-25-96
INV. NO. 46820
10-11