

4-032409

API Number: 15-039-20,008 -00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

S2 SE NE / 4 SEC. 06, 03, 29 W
2970 feet from S section line
660 feet from E section line

Operator license# 4315 (Expired 04-30-1991)

Lease: Amanda "A" Well # 1 *Fee waived*
County: Decatur

Operator: Formerly (Brazos Pet. Co.)
500 W. Wall Street
Address: P.O. Box 1782
Midland, Texas 79702
915-682-6644

4/6

Well total depth 3964 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 239 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: R.L. Hrbek License# 31274

Address: Rt. 1 - Box 11 - Merino, CO 80741

Company to plug at: Hour: P.M. Day: 6 Month: April Year: 2000

Plugging proposal received from: Carl Goodrow - KCC - R.L. Hrbek

Company: KCC and R.L. Hrbek Phone: -

Were: Order 8 yards Redimix Concrete.
Order bottom plug and 5 sxs common cement.
Exempt Area.
The operator cannot be found and this lease is on the list for "Fee Fund".
The contractor agreed to plug out and clean up the lease for the equipment.
The landowner is in full agreement and very pleased.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:00 P.M., Day: 6 Month: April, Year: 2000

Actual plugging report: 8 5/8" set at 239' w/150 sxs cwc. 5 1/2" set at 3963' w/100 sxs.
Prod. Perfs 3771' - 3774'. Set plug at 3720' with 5 sxs common cement on plug with bailer.
Shot and recovered 1600' of 5 1/2". Load hole with 8 yards Redimix to surface. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 5/19/00
INV. NO. 61751

Da May report

RECEIVED
STATE CORPORATION COMMISSION

Form CP-2/3

APR 28 2000

CONSERVATION DIVISION
Wichita, Kansas

