

State of Kansas



15-039-20292-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1974

CONSERVATION DIVISION
Wichita, Kansas

9-23-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Keith Gallatin of Indigo Drilling Company has this date requested permission to plug the following described well:

Mr. Gallatin guarantees payment of the plugging fee.

Operator's full Name: Kelly-Hughes Trust,

Complete Address: 3521 North Central Ave., Phoenix, Arizona.

Lease Name: Vavroch Well No. 1

Location: CSW-NE Sec. 34 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 4493' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gallatin was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with --
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1425' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent