

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20292-00-00

SEP 23 1974

CONSERVATION DIVISION
Wichita, Kansas

9-23-74

Operator's Full Name Kelly-Hughes Trust,

Complete Address 3521 North Central Avenue, Phoenix, Arizona. 85012

Lease Name Vavroch Well No. 1

Location CSW-NE Sec. 34 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 4493'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Indigo Drilling Company,

Address Box #83, Oberlin, Kansas. License No.

Operation Completed: Hour 4:45 AM Day 19 Month 9 Year 1974

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with --
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1425' and displaced 110 Cu. Ft. cement
thru DP from 1425' to 1100'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/8 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/23/74

INV. NO. 9943-W