

RECEIVED
KCC DISTRICT #2

AUG 26 2004

WICHITA, KS

01021-00-01

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 095-90477-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; If no API # was issued,

indicate original spud or completion date _____

Well Operator: VESS OIL CORPORATION KCC License #: 5030

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: (316) 682-1537 X103

Lease: Elmer Hibbs Well #: 4 Sec. 35 Twp. 29S S. R. 07 East West

C - E/2 NW SE Spot Location / QQQQ County: Kingman

~~1080~~ 2089 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~4650~~ 1752 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # D-21,863 CNII Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 251' Cemented with: 200 Sacks

Production Casing Size: 5-1/2" Set at: 4163' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Miss Chert Perfs: 4107-17', 4125-30', 4133-42', CIBP 3950' 10' cmt

retainer 3660', sqz 3700-02' 100 sx TOC 2900', Lansing 3570-3594'

Elevation: 1480/1486 (GL) / (K.B.) T.D.: 4164' P.B.T.D.: 3660' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole (packer @ 3587')

Proposed Method of Plugging (attach a separate page if additional space is needed): 8/17/04 Steve VanGeisen: 50 sx Class A, 3% cc, btm plug @ 3570'; Perf btm salt section - 1250', 35 sc Class A, 3% cc. sqz in, leave 50' in csg, perf top of salt: 700' - 35 sx, Class A, 3% cc, sqz in, leave 50' in casing. Perfs at 300'. Circ. cement up 8-5/8 and 5-1/2 annulus and fell inside

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 aL, sec. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Tracy Black

Phone: (316) 215-1873

Address: 4748 NE 160th Avenue City / State: Cheney, KS 67025

Plugging Contractor: United Cementing and Acid, Inc. KCC License #: 30437

Address: 4610 W. 6th, El Dorado, KS 67042 Phone: (316) 321-4680

Proposed Date and Hour of Plugging (if known?): 8/18/04 8:00 a.m. Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/17/04 Authorized Operator / Agent: Casey Beata (Signature)

4/05

9/04