



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas
1-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Ward Sauvage

Complete Address: Oberlin, Kansas

Lease Name: Sauvage Well No. 1

Location: CNW-SW Sec. 28 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3970' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

288'--7" OD Surface casing, cement circulated with 135 Sx. (6 1/4" Hole). Dakota section from 1425' to 1600'.

Circulate hole with heavy mud. Pull DP to 1625' and displace 65 Sx. cement thru DP. Pull DP to 300' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent