



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1964
7-13-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jack Lowry of Burch Exploration, Ltd., has this

date requested permission to plug the following described well:

Forest Oil Corp.

Mr. Lowry guarantees payment of the plugging fee.

Operator's full Name: Forest Oil Corporation,

Complete Address: 1020 Hales Building, ^{OKLAHOMA CITY, OKLAHOMA} Wichita, Kansas.

Lease Name: Ruzicka Well No. 2

Location: CSW-NW Sec. 21 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3918 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lowry was instructed to plug the well as follows:

241'--8 5/8" Surface pipe, cement circulated with 185 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	240' with $\frac{1}{4}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent