



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1970

CONSERVATION DIVISION  
Wichita, Kansas

11-2-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Charles Well No. 1

Location: CSE-NE Sec. 29 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3960' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

258'--8 5/8" Surface casing, cement circulated with 185 Sx.  
3960'--5 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3264' (Temp. Survey). Well plugged back to 3925'. Top perforations from 3783' to 3786'.

Push plug to 3700', sand to 3675' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent