



15-039-2012600-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
6-22-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Gemeroth Well No. 1

Location: NW-NE-SE Sec. 29 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 2530' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

288'---8 5/8" Surface casing, cement circulated with 235 Sx.  
Top of Dakota section @ 1400'.

Circulate hole with heavy mud. Pull DP to 1625' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent