



15-039-20098-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling Drlg. Co has this  
date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: XX Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Charles Well No. 2

Location: CNE-NE Sec. 29 Twp. 3 Rge. (E)(W) 28

County: Decatur Total Depth 3956' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

261'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1800'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

JUL 23 1969

CONSERVATION DIVISION  
Wichita, Kansas

7-23-69

Very truly yours,

Conservation Division Agent