

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20035-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas
1-15-68

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ward Sauvage,

Complete Address: Oberlin, Kansas. 67749

Lease Name Sauvage Well No. 1

Location CNW-SW Sec. 28 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Abercrombie Drilling, Incorporated,

Address: 801 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 1:00 PM Day 10 Month 1 Year 1968

The Above well was plugged as follows:

288'--7" OD Surface pipe, cement circulated with 135 Sx. (6 1/4" Hole).

Dakota section from 1425' to 1600'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 65 Sx. cement thru

DP from 1625' to 1300'. Pulled DP to 300' and displaced 15 Sx. cement thru DP from

300' to 225'/ Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. B. Nichols

Well Plugging Supervisor

DATE 1/15/68

INV. NO. 7102-W