

15-039-20007-00-00

Form CP-3
Rev. 6-26-62

KANSAS

TP
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

APR 3 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Burch Exploration, Incorporated.

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name Vavroch Well No. 1

Location CSE-SE Sec. 28 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3990

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Abercrombie Drilling, Incorporated.

Address: 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 4:30PM Day 28 Month 3 Year 1967

The Above well was plugged as follows:

266'--7" OD Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 600' and displaced 10 Sx.

cement thru DP. Heavy mud to 250', set plug with 1/4 sack hulls and dis-

place 10 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 8 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 4/3/67
INV. NO. 4990-W



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Burch Exploration, Incorporated,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name: Vavroch Well No. 1

Location: CSE-SE Sec. 28 Twp. 3 Rge. (E)(W) 28

County Decatur Total Depth 3990 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

266'--7" OD Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 600' and 10 Sx. cement.

"	"	250'	with $\frac{1}{4}$ sk. hulls &
			10 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			8 Sx. cement.

Very truly yours,

Conservation Division Agent