

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

18-039-20098-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company.

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Charles Well No. 2

Location CNE-NE Sec. 29 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3956'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Incorporated.

Address 801 Union Center Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 7:00 AM Day 16 Month 7 Year 1969

The above well was plugged as follows:

261'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 100 Sx. cement thru
DP from 2000' to 1675'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 23 1969

CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. Fehle
Well Plugging Supervisor

DATE 7/23/69
INV. NO. 128-W

17 23-69