

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

15-039-20126-0000

6-22-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Gemeroth Well No. 1

Location NW-NE-SE Sec. 29 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 2530'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 AM Day 18 Month 6 Year 1970

The above well was plugged as follows:

288'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pull DP to 1625' and displaced 100 Sx. cement thru
DP from 1625' to 1300'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 6/22/70
INV. NO. 2076-4