

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1970
CONSERVATION DIVISION
Wichita, Kansas

15-039-30092-00-00

11-2-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Charles Well No. 1

Location CSE-NE Sec. 29 Twp. 3 Rge. (E) (W)28

County Decatur Total Depth 3960'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:00 AM Day 23 Month 10 Year 1970

The above well was plugged as follows:

258'--8 5/8" Surface casing, cement circulated with 185 Sx.

3960'--5 1/2" Production casing cemented on bottom with 125 Sx. Top of Cement @ 3264' (Temperature Survey). Well Plugged back to 3925'. Top perforations from 3783' to 86.

Pushed plug to 3700', sanded to 3675' and set 5 Sx. cement with dump bailer. Pulled

5 1/2" casing (1500') and squeezed well initially with 5 sacks hulls and 6 sacks gel and

followed with 100 Sx. cement from 1625' to 1300' then 25 gel from 1300' to 275' and

followed with 25 Sx. cement from 275' to 200' then 4 sacks gel from 200' to 40' and

finally 15 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-450#.

Final shut-in pressure-250#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/2/70

INV. NO. 2788-W