

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-30066-0001

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas
2-27-74

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Charles Well No. 1-SWD
Location NW CNE-NE Sec. 29 Twp. 3 Rge. (E) (W) 28
County Decatur Total Depth 2349'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 5:30 PM Day 21 Month 2 Year 1974

The above well was plugged as follows:

375'--8 5/8" Surface casing, cement circulated with 200 Sx.
2349'--4 1/2" casing cemented on bottom with 25 Sx. 4 1/2" casing perforated @ 1652' and
squeezed to cellar with 275 Sx. cement. Disposing thru perforations from 2175' to
2195'.

Squeezed well with 1 sacks hulls, 8 sacks gel and finally 90 Cu. Ft. cement. Max-
imum pump-in pressure-1100#. Final shut-in pressure-700#. (Mudding and cementing
operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Dicks
Well Plugging Supervisor

DATE 2/27/74
INV. NO. 8650-W