

DISTRICT CONSERVATION AGENT'S REPORT

15-039-00028-00-01

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION C NE NE

SEC. 32 TWP. 3 RGE. 28

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Vernon

Operator Westgate Greenland Oil Address Wichita, Kans

Field _____ County Decatur

Old T. D. 4400'
Total Depth New 4028' Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 403' circulated with cement. 5 1/2" at 4028' with
75 sax cement behind - Perforated 3868' - squeezed with 4 7/8
sax Pozmix Cement - set bridging plug at 3100. rock and
5 sax cement - pulled 1600' 5 1/2" - filled with mud to 403' -
set rock and 15 sax cement - mud to 35' - set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC. 327-3-222
BOOK PAGE 54 LINE 24

RECEIVED
STATE CORPORATION COMMISSION
DEC - 9 1952
CONSERVATION DIVISION
Wichita, Kansas

Edon J. ...
District Conservation Agent
Date 12-6-52

12-9-52