

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20256-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

1-26-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Tomlinson Oil Company, Incorporated,

Complete Address Suite 1030, 200 West Douglas, Wichita, Kansas.

Lease Name Tilden Well No. 1

Location ONE-SE Sec. 32 Twp. 3 Rge. (E) (W) 28

County Decatur Total Depth 3952'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas License No.       

Operation Completed: Hour 4:00 AM Day 23 Month 1 Year 1973

The above well was plugged as follows:

250'---8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 110 Cu. Ft. cement  
thru DP from 1625' to 1300'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 1/30/73

INV. NO. 6917-W