

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20500-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 22-3S-28W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: SCHWEDER Well Number: 22-42  
County: DECATUR Total Vertical Depth: 3980 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3978 w/350 sxs cmt  
Surface Casing Size: 8.625 feet: 218 w/175 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/29/2003 10:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Plug 4 1/2" casing to volume and pressure.  
Plug 8 5/8" to volume and pressure.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/29/2003 12:00 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Perforations at 3840' - 3844' and 3732' - 3736'.  
8 5/8" S.P. set at 218.73' w/175 sxs. 4 1/2" set at 3978' w/350 sxs cement.  
Connect to 4 1/2" production casing - pumped 235 sxs cement with 500# hulls.  
Max. P.S.I. 150#. S.I.P. 0#.  
Connected to 8 5/8" S.P. Pumped 65 sxs cement with 100# hulls.  
Max. P.S.I. 150#. S.I.P. 0#.

RECEIVED  
SEP 05 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

OXFORD EXPLORATION COMPANY . REPLACEMENT CARD: 22-3-28W  
 1030 DENVER CLUB BLDG. #22-42 SCHWEDER NW NW NW  
 DENVER, CO. 80202  
 CONTR MURFIN DRILLING CO. CTY DECATUR

GEOL JAMES L. REEVES FIELD DECATUR CENTER EXT (1/8 E)

E 2688 KB CM 5/10/80 CARD ISSUED 8/21/80 IP P 30 BOPD & NW  
 2683 GL LKC 3732-3844 OA

+	+	+
+	+	+

API 15-039-20,500

LOG	TOPS	DEPTH	DATUM
ANH		2372	+ 316
HEEB		3659	- 971
TOR		3692	-1004
LKC		3703	-1015
B KC		3922	-1234
RTD		3980	-1292

8-5/8" 218.73/175sx, 4 1/2" 3978/350sx

DST (1) 3734-60(LKC)/30-30-120-30,  
 50' CL GSY O, 50' OCM, 15' CL O, SIP  
 549-500#, FP 48-50/50-58#, FHP  
 1885#

MICT - CO, PF (LKC) 3840-44, 3732-36  
 W/2 SPF, SWB DWN W/GSO, NAT, POP, P 30  
 BOPD, NW, 6/7/80

INFO RELEASED: 7/29/82 - WAS  
 OPERATIONS SUSPENDED

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS