

10-9-87 15-039-19033-00-01

6 030967

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1963  
SW SW, SEC. 21, T 3 S, R 28 W/E  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Harmon Well # 2

Operator: Halliburton Oil Prod Co.  
Name & Address: Box 10  
Stafford, Kansas 67578

County Decatur 127.40  
Well Total Depth 3920 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well  Gas Well  Input Well  FOR KCC app 8.27.04 SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 9 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing Pulling (phone)

were: 8 5/8" set at 237' w/215 sks 5 1/2" set at 3919' w/200 sks. Perf 3747' - 3893'.  
Order sand and Common Cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dical Cement Blend. 500# Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30PM Day: 9 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3700' w/5 sks Common Cement on sand w/bailer. 4 shots at 2200' 2000' 1800' and 1700'. Recovered 1700' of 5 1/2" casing. Squeeze 8 5/8" casing w/200 sks Cement Blend w/500# Hulls mixed in. Max Psi 300# Close in Psi 200# Plug complete.

STATE CORPORATION COMMISSION  
NOV 30 1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 12-4-87

Carl Goodrow

INV. NO. 19111

FORM CP-2/3 Rev. 01-84

LR