

6 030969

10-9-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15966 15-039-30056-0001

C NE NW, SEC. 21, T 3 S, R 28 W/Ex

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Ruzicka Well # 3

Operator: Halliburton Oil Prod. Co.
Name &

County Decatur 129.68

Address Box 10

Well Total Depth 3990 feet

Stafford, Kansas 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 7 feet 272

Abandoned Oil Well Gas Well _____ Input Well EOP KCOR 1327-04 SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 9 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone) _____

were: 7" set at 272' w/135 sks. 4 1/2" set at 3987' w/125 sks. Perf 3752' - 3947'.

Order sand and Common Cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dical Cement Blend 5 sks Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15PM Day: 9 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3700' w/4 sks Common Cement on sand w/bailer.

3 shots at 2200' 2000' and 1800'. Recovered 1800' of 4 1/2" casing.

Squeezed 7" casing w/100 sks Cement Blend w/500# Hulls mixed in.

Max Psi 800# Close in Psi 200# Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 12-8-87

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)

DB

INV. NO. 19201