

10-9-87 15-039-30066-00-00

To: 6 030966  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1966  
150 W NE NE  
SEC. 21, T. 3, S. R. 28  
4620 feet from S section line  
810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988  
Operator: Halliburton Oil Prod Co.  
Name & Address: Box 10  
Stafford, Kansas 67578

Lease Name Witt Well # 3  
County Decatur 128.70  
Well Total Depth 3960 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 7" feet 270

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, Kansas

Company to plug at: Hour: AM Day: 9 Month: Oct. Year: 19 87

Plugging proposal received from Mark  
(company name) Kelso Casing (phone)

were: 7" set at 270' w/125 sks 4 1/2" set at 3958' w/125 sks. Perf. 3925'. Order sand and Common Cement Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dical Cement Blend. 5 sks Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:50AM Day: 9 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3875' w/4 sks Cement on sand w/bailer. 3 shots at 2200' 1500' and 1317'. Recovered 1317' of 4 1/2" casing. Squeeze 7" w/200 sks Cement Blend w/500# Hulls mixed in. Max Psi 300#. Close in Psi 200#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
11-30-87  
15030966

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-87  
INV. NO. 19107

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow