

4-031751

9-9

43 R

15-039-20246-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1972

SE SE NW /4 SEC. 21, 03 S, 28 W  
2970 feet from S section line  
2970 feet from E section line

Operator license# 5988

Lease Decatur Co. Unit well # 1  
WSW

Operator: Halliburton Oil Producing

County Decatur

Address: P.O. Box 10  
Stafford, Kansas 67578

Well total depth 2934 feet <sup>95.35</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 242 feet

Aband. oil well   , Gas well   , Input well   , SWD   , D & A    WSW X

Plugging contractor: Kelso License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 9 Month: September Year: 92

Plugging proposal received from: Vernon

Company: Kelso Phone:                                 

Were: Order 325 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open by wireline.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[    ], None[    ]

Completed: Hour: 11:50A.M., Day: 9, Month: September, Year: 92

Actual plugging report: 10 3/4" set @ 242' w/ 300 sx. cwc. 7" set @  
2404' w/250 sx. cwc. Squeezed 7" w/242 sx. cement blend w/450# hulls  
mixed in to Max. P.S.I. 500#. Close in P.S.I. 500#. Test backside  
w/42 sx. to Max. P.S.I. 500#. Close in P.S.I. 500#.

RECEIVED  
STATE CORPORATION COMMISSION

SFB 24 1992  
9-24-92

Remarks:     
Condition of casing(in hole): GOOD X BAD    Any plug: YES NR NO     
Bottom plug(in place): YES   , CALC   , NO    Dakota plug: YES X, NO     
Plugged through TUBING   , CASING X. Elevation:    GL

   did [X], did not [  ] observe the plugging. Carl Goodrow

INVOICED  
DATE 10-2-92  
INV. NO. 36309

HO  
(agent)