

10-9-87 15-039-00410-00-00

6 030968

API NUMBER 15- 1964

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE, SEC. 21, T 3 S, R 28 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Witt Well # B-1

Operator: Halliburton Oil Prod Co.
Name & Address: Box 10

County Decatur 129.51

Well Total Depth 3985 feet

Stafford, Kansas 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 9 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone)

were: 8 5/8" set at 248' w/190 sks. 4 1/2" set at 3984' w/225 sks. Perf 3754' - 3943'.

Order sand and Common Cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dical, Cement Blend. 5 sks Hulls. Halliburton Cement Co. LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45 PM Day: 9 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3700' w/4 sks Common Cement on sand w/bailer.

3 shots 2000' 1200' 819'. Recovered 819' of 4 1/2" casing. Squeeze 8 5/8" w/200 sks

Cement Blend w/500# Hulls mixed in. Max Psi 300#. Close in Psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
I will observe this plugging.

DATE 12-4-87

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

INV. NO. 19112