

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-089-19033-00-01

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

API NUMBER _____
 LEASE NAME Harmon
 WELL NUMBER #2
 _____ Ft. from S Section Line
 _____ Ft. from E Section Line
 SW SW
 SEC. 21 TWP. 3 RGE. 28W (E) or (W)
 COUNTY Decatur
 Date Well Completed 10-20-87
 Plugging Commenced 9-30-87
 Plugging Completed 10-9-87

LEASE OPERATOR Halliburton Oil Producing Company
 2915 Classen Blvd. Suite 300
 ADDRESS Oklahoma City, Okla. 73106

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well oil EOR ^{app} rec 27.04
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	237'	none
				5-1/2"	3919'	1692'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3700' and 5 sacks cement. Shot pipe @2214', 2021', 1803', 1692', pulled a total of 54 joints of 5-1/2" casing. Plugged surface with 5 sacks hulls and 200 sacks econolite.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso CAsing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso
 (Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1987

James Hoover
 Notary Public

My Commission Expires: _____



OCT 13 1987