


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County. Sec. 32 Twp. 38 Rge. 28W (W)
Location as "NE/CNW/SW" or footage from lines 150' SE Center of SE SE
Lease Owner Cities Service Petroleum Company
Lease Name Tilden Well No. 1
Office Address Box 553, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/11/1962
Application for plugging filed 2/11/1962
Application for plugging approved 2/12/1962
Plugging commenced 2/12/1962
Plugging completed 2/12/1962
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3955 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	240'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole 3955' to 550' w/heavy mud thru drill pipe,
Spotted 20 sx. cement at 550' thru drill pipe by Howco,
Filled hole 550' to 230' w/heavy mud thru drill pipe,
Spotted 20 sx. cement at 230' thru drill pipe by Howco,
Filled hole 230' to 35' w/heavy mud thru drill pipe,
Placed cotton seed hull bridge w/drill pipe at 35',
Filled hole from 35' to surface w/10 sx. cement,
Complete 2/12/62, 7:30 A.M.

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1962
CONSERVATION DIVISION
Wichita, Kansas
3-2-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Burch Drlg. Company
Address 1011 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
M. M. Hardin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin
Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1962
W. D. Smith
My commission expires March 12, 1963 Notary Public.



WELL RECORD

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Petroleum Co. WELL # 1 FARM Tilden

LOCATION 554' North and 554' West of SE Corner

Section 32, Township 3, Range 28W

ELEV. 2730 D.F. CO. Decatur STATE Kansas

IP. Dry hole. P. and A. February 12, 1962.

PERFS.....

FRAC..... ACID None

T.D. 3955' PBTD..... GRAV/OOR.....

DRLG. COMM. February 1, 1962 COMP. February 11, 1962 CONTRACTOR Burch Drig. Co., Inc.

CASING RECORD:

8-5/8" at 240' with 250 sacks cement.

FORMATION RECORD:

sand and shale	0-240
shale	2136
sand	2220
shale	2413
Anhydrite	2444
shale and lime	3679
lime and shale	3805
shale and lime	3955 T.D.

RECEIVED
STATE CONSERVATION COMMISSION

MAR 2 1962

CONSERVATION DIVISION
Kansas

32-62