

15-039-00028-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Decatur County, Sec. 32 Twp. 3S Rge. (E) 28(W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Westgate-Greenland Oil Company

Lease Name Vernon Well No. 1

Office Address 1009 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed October 21, 1952 19

Application for plugging filed October 23, 1952 19

Application for plugging approved October 24, 1952 19

Plugging commenced November 14, 1952 19

Plugging completed December 6, 1952 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	403	8 5/8"	403	none
Kansas City		0	4028.5	5 1/2"	4028.5	1602

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made solid with rock @ 3100 feet
Ran 5 sacks cement from 3100 to 3065 feet
Filled with mud to 420 feet and rock to 408 feet
Ran 15 sacks cement from 408 to 380 feet
Filled with heavy mud from 380 to 35 feet and made solid with rock,
Capped with 10 sacks cement to cellar

RECEIVED
DEC 20 1952
CONSERVATION DIVISION
Wichita, Kansas
12-20-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service

Address 102 West 18th Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Don Allen, (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Allen
1009 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1952

Esther Russell
Notary Public.

My commission expires May 25, 1953.

PLUGGING
FILE SEC 227-3 R-224
BOOK PAGE 54 LINE 24

13-039-00028-00-01

DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Westgate Drilling Corporation
 FARM: Vernon #1 (old well drilled by Phillips Petr. in 1942)
 LOCATION: Center NE NE Sec. 32-38-28W Decatur County, Kansas
 COMMENCED: October 10, 1952 - Rotary
 October 14, 1952 - Cardwell
 COMPLETED: October 12, 1952 - Rotary
 October 21, 1952 - Cardwell
 ELEVATION: 2746 DF

0	to	175	Sand
175	to	296	Broken sand and clay
296	to	616	Soft shale
616	to	1325	Soft shale and shells
1325	to	1535	Shale and shells
1535	to	1660	Broken sand
1660	to	1740	Sandy shale
1740	to	1925	Shale
1925	to	2025	Chert, lime and shale
2025	to	2080	Green shale streaks, Chert
2080	to	2145	Sand and shale-chalk
2145	to	2160	Shale
2160	to	2425	Shale
2425	to	2460	Anhydrite and lime
2460	to	2512	Shale
2512	to	2729	Shale and shells
2729	to	2838	Lime and shale
2838	to	3060	Shale and shells
3060	to	3134	Lime and shale
3134	to	3164	Shale
3164	to	3189	Sandy lime
3189	to	3298	Lime and shale
3298	to	3382	Lime
3382	to	3431	Lime and shale
3431	to	3497	Shale and sandy lime
3497	to	3568	Lime
3568	to	3628	Broken lime and shale
3628	to	3721	Lime
3721	to	3751	Broken lime and shale
3751	to	3794	Lime and chert
3794	to	3804	Lime
3804	to	3813	Lime and chert
3813	to	3844	Lime and shale
3844	to	3879	Lime
3879	to	4008	Lime and shale
4008	to	4142	Shale
4142	to	4206	Shale and sandy shale
4206	to	4229	Shale
4229	to	4262	Chert
4262	to	4272	Chert, shale and sand
4272	to	4276	Shale
4276	to	4346	Lime and shale
4346	to	4385	Lime-shale and sand
4385	to	4394	Lime
4394	to	4400	Granite

(above formations taken from Driller's log from Phillips Petr)

Phillips set 403' of 8 5/8" surface. Cemented with 200 sacks cement (back in 1942)

Washed down hole to 4099 and set 5 1/2" casing at 4028.5' Cemented with 75 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 32 T 3 R 2824
BOOK PAGE 54 LINE 24

15-039-00028-00-01

TOPS: Anhydrite 2425 Topeka 3603 Lansing 3751

Perforated 22 shots 3868 $\frac{1}{2}$ -73, slightly oil cut mud,
2 shots 3848-50,
6 shots 3842-44, more mud, no oil.

Squeezed it off 3840-3873 with 475 sacks cement.

Perforated 36 shots 3868-76, slight show oil in mud
1000 GA, swabbed 2 BWP, still light show oil, tested
24 hours, perforated 6 shots 3842-44,

- 6 shots 3848-50, very lt show oil,
- 12 shots 3834 $\frac{1}{2}$ -38 $\frac{1}{2}$, no show,
- 12 shots 3806-10, no show,
- 12 shots 3791-95, no show,
- 12 shots 3764-68, Very lt show heavy oil,
- 12 shots 3750-54, no show,
- 12 shots 3903-07, no show,
- 12 shots 3950-54, no show,

Swabbed every hour and tested for 12 hours, continued
swabbing 6 hours after last shots.

Lane Wells Log and Schlumberger Microlog run.


Dry and Abandoned.

C E R T I F I C A T E

I, G. E. Bitler, do hereby certify that the above and
foregoing is a true and correct copy of the log of the
Vernon No. 1, Center NE NE Section 32-3S-28W, Decatur
County, Kansas, as reflected by files of the Westgate-
Greenland Oil Company.


G. E. Bitler

Subscribed and sworn to before me, a Notary Public,
within and for Sedgwick County, Kansas, this 23rd day
of October, 1952.


Esther Unsell, Notary Public

My commission expires May 25, 1953.