


15-039-20098-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Decatur County, Sec. 29 Twp. 3S Rge. (E) 28 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Okmar Oil Company  
Lease Name CHARLES Well No. 2  
Office Address 1130 Wichita Plaza; Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 16, 19 69  
Application for plugging filed (verbally) July 16, 19 69  
Application for plugging approved (verbally) July 16, 19 69  
Plugging commenced July 16, 19 69  
Plugging completed July 16, 19 69  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well 3956 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	272'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug @2000' w/100 sx. cement;  
Set 2nd plug @ 275' w/ 20 sx. cement;  
Set top plug @ 40' w/ 10 sx. cement.  
Job was completed 7:00 a.m., 7-16-69

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas

7-18-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address (office) 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie  
801 Union Center; Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 69

My commission expires July 15, 1972

Sue J. Blunck  
Sue J. Blunck, Notary Public.

15-039-20098-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Okmar Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: CHARLES #2  
 LOCATION: C NE NE, Sec. 29-3S-28W  
 Decatur County, Kansas  
 SPUD DATE: July 8, 1969  
 COMPLETION DATE: July 16, 1969

0	60	Clay
60	180	Sand
180	1390	Shale
1390	1820	Shale & Shells
1820	1885	Sand
1885	1945	Shale
1945	2142	Shale & Gyp
2142	2229	Sand
2229	2416	Shale
2416	2450	Anhydrite
2450	2720	Shale
2720	3353	Shale & Lime
3353	3656	Lime & Shale
3656	3956	Lime
	3956	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 18 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 7-18-69

Drilled 280' of 12½" surface hole and set 8-5/8" csg. @271.71 w/200 sx. cement. Cement circulated. Plug was down 5:00 p.m , 7-8-69.  
 Dry & Abandoned.

Sample Formation Tops

Elevation

Not Available

Not Available

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the Log of the #2 CHARLES, C NE NE, Sec. 29-3S-28W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: A. L. Abercrombie  
 A. L. Abercrombie  
 President

Sworn to before me, a Notary Public, in and for the county and state above mentioned, as of this 17th day of July, 1969.

Sue J. Blunck  
 Sue J. Blunck, Notary Public

My Commission Expires: July 15, 1972