

NOV 13 1980

15-039-20534-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS, 67202

Decatur County, Sec. 27 Twp. 3S Rge. 28W 1/4/4
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
100' N of Apx. C SE/4 NE/4

Lease Owner Gear Petroleum Company, Inc.
Lease Name Janousek-Laidig Well No. 1
Office Address 300 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
D & A


Date Well completed November 5, 1980
Application for plugging filed November 5, 1980
Application for plugging approved November 5, 1980
Plugging commenced November 5, 1980
Plugging completed November 5, 1980

Reason for abandonment of well or producing formation
D & A

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,020'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	283.27'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plugged well @ 1450 w/70 sx cement
@ 280 w/20 sx cement
Bridge plug @ 40 w/10 sx cement
5 sx cement in rathole

NOV 17 1980
CONSERVATION DIVISION
Wichita, Kansas
11-17-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~owner~~ or ~~operator~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1980.

My commission expires _____ Notary Public.



NOV 13 1980

15-039-20534-00-00

DRILLERS LOG

No. 1 Janousek-Laidig

CASING RECORD:	COMPANY:	Gear Petroleum Company, Inc.	DESCRIPTION:
8 5/8" @ 291' w/190 sx cement	CONTRACTOR:	Red Tiger Drilling Company	100' N of Apx. C SE/4 NE/4 Sec. 27-T3S-R28W Decatur County, Kansas
D & A	COMMENCED:	October 29, 1980	
TOTAL DEPTH: 4,020'	COMPLETED:	November 5, 1980	ELEVATION: 2,725' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	296	
Shale	296	1590	
Sand & Shale	1590	1790	
Shale	1790	1850	
Sand & Shale	1850	1892	
Shale & Sand	1892	2160	
Shale	2160	2300	
Red Bed	2300	2431	
Anhydrite	2431	2465	
Shale	2465	2510	
Shale & Lime Streaks	2510	2955	
Shale & Lime	2955	3175	
Lime & Shale	3175	3457	
Shale & Lime	3457	3580	
Lime	3580	4020	
RTD		4020	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 12th day of November, 1980.

Joyce A. Baer
Notary Public

