


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-039-20459-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Decatur County, Sec. 22 Twp. 3S Rge. 28W (EX) (W)  
Location as "NE/CNWxSWx" or footage from lines C SE NE  
Lease Owner Vincent Oil Corporation  
Lease Name Orr Well No. #1  
Office Address 230 O.W. Garvey Bldg., 200 W. Douglas, Wichita, KS  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole 67202  
Date well completed August 1, 19 79  
Application for plugging filed Yes 19  
Application for plugging approved 19  
Plugging commenced 19  
Plugging completed 11:45 A.M., August 1, 19 79  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 set @ 1400' w/70 sx. cement  
Plug #2 set @ 240' w/20 sx. cement  
Plug #3 set @ 40' w/10 sx. cement

RECEIVED  
CORPORATION COMMISSION

AUG - 8 1979

8-8-79

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John O. Farmer, Inc.  
Address Box 352, Russell, KS 67665


STATE OF Kansas, COUNTY OF Russell, ss.  
John O. Farmer (Employee or Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer  
Box 352, Russell, KS 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 79

Connie Lynn Anderson  
Notary Public.

March 29, 1983



15-039-20459-00-00

Operator Vincent Oil Corporation (C S E N E)  
 Well No. #1 Lease Name Orr  
 Dry Hole.  
 S 22 T 3S R 28 W - Decatur County, Kansas

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	-0-	325	LOG TOPS;	
Shale & Sand	325	2142	Anhydrite	2430 (+ 299)
Gypsum	2142	2153	Severy	3592 (- 863)
Sand	2153	2238	Topeka	3617 (- 888)
Red Bed	2238	2430	Heebner	3732 (-1003)
Anhydrite	2430	2463	Toronto	3764 (-1035)
Shale & Shells	2463	2581	Lans.-K.C.	3776 (-1047)
Shale & Lime	2581	3832	Bs. K.C.	3970 (-1241)
Lime	3832	3990	Log T.D.	3992
			Rotary T.D.	3990
Lost Circ. @ 600 ft.				
Drill Stem Test #1 - 3788-3832 ft. 30-30-30-30 min. Weak blow increasing to fair. Recovered 50 ft. watery mud and 250 ft. salt water. IFP 31-104#, ISIP 1274# FFP 104-167#, FSIP 1261#				
Drill Stem Test #2 - 3830-3935 ft. Packer failure				
Drill Stem Test #3 - 3825-3935 ft. 45-45-45-45 min. Weak blow. Recovered 180 ft. mud with rainbow of oil. IFP 73-115#, ISIP 959# FFP 115-178#, FSIP 938#				

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1979

CONSERVATION DIVISION  
Wichita, Kansas

8-10-79

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_  
 Signature John O. Farmer, Inc.  
 Title President  
 Date August 7, 1979