



15-039-20233-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
4-25-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Zander Well No. 1

Location: 200' No. of CNW-NW Sec. 10 Twp. 3 Rge. (E)(W) 29

County: Decatur Total Depth 3880' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

230'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1275'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent