



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:  
Union Texas Petr. Co.,

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum Company,

Complete Address: 1740 Broadway, Denver, Colorado.

Lease Name: Boettger Well No. 1

Location: NW-NW-SE Sec. 5 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 4210 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

211'--8 5/8" Surface pipe, cement circulated.  
3913'--5 3/8" Production casing cemented with 125 Sx. Top per-  
forations from 3702' to 3703'. Well plugged back to 3770'.

Push plug to 3690' and set 5 Sx. cement with dump bailer.

Set bridge @ 300' and fill to bottom of cellar with Redi-Mix.

Very truly yours,

A. L. Nichols  
Conservation Division Agent