

State of Kansas



15-039-00550-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 3 1966
10-3-66
CONSERVATION DIVISION
Wichita, Kan.

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Bulldog Pipe and Supply Company,

Complete Address: Box #1153, Tulsa, Oklahoma.

Lease Name: Boettger Well No. 2

Location: SE-SE-SE Sec. 5 Twp. 3 Rge. (E)(W) 29

County Decatur Total Depth 3940 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

165'--8 5/8" Surface pipe, cement circulated.
3930'--5 1/2" Production casing cemented. Bottom hole completion.

Sand well back to 3910' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 30 sacks gel followed with 75 sacks cement.

Very truly yours,

Conservation Division Agent