



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

8-3-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Csg. Pulling Co. Inc., has this

date requested permission to plug the following described well:

Union Texas Petroleum

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum.

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name: Pollnow Unit Well No. 3

Location: NE-NE-SW Sec. 5 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3931 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

271'--8 5/8" Surface pipe, cement circulated. 3926'--5 1/2" production casing cemented with 100 Sx. Well plugged back to 3850. Top perforations at 3746'.

Sand well back to 3720' and set 4 Sx cement with dump bailer.

Circulate heavy gel mud at 660', pull 5 1/2" to 600' and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 270' and displace 20 Sx. cement thru 5 1/2".

Pull 5 1/2", set bridge at 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. D. Dickels
Conservation Division Agent